

PHOTOGRAPHIC INTERPRETATION REPORT

ICBM COMPLEX TEYKOVO, USSR LAUNCH AREAS D, E, F, AND G

Declass review-NIMA/DOD



CIA




DIA

Handle Via **TALENT - KEYHOLE** Control Only

WARNING

This document contains classified information affecting the national security of the United States within the meaning of the espionage laws U. S. Code Title 18, Sections 793 and 794. The law prohibits its transmission or the revelation of its contents in any manner to an unauthorized person, as well as its use in any manner prejudicial to the safety or interest of the United States or for the benefit of any foreign government to the detriment of the United States. It is to be seen only by personnel especially indoctrinated and authorized to receive TALENT-KEYHOLE information. Its security must be maintained in accordance with KEYHOLE and TALENT regulations.

NATIONAL PHOTOGRAPHIC INTERPRETATION CENTER



TOP SECRET

TCS-7559/64
NPIC/R-700/64

ICBM COMPLEX, TEYKOVO, USSR
LAUNCH AREAS D, E, F, AND G

25X1D

This report presents information on Launch Areas D (Site 4),* E (Site 5), F (Site 6), and

G (Site 7) of the Teykovo ICBM Complex based on KEYHOLE photography of [REDACTED] and updating that given in NPIC/R-205/64, dated March 1964. 1/

*TDI site designators are shown in parentheses.

25X1D

LAUNCH AREA D

Launch Area D (56-59N 40-39E), in a wooded area 6.7 nautical miles (nm) northeast of the complex support facility, consists of a completed Type IIF launch site and a site support facility (Figure 1). It was first seen on photog-

axis of the pad. A small unidentified mound, forward of the canted ready building, may be a buried tank. [REDACTED]

25X2

25X2

25X2

[REDACTED] There is also a large borrow pit about 2,000 feet east of the site.

Construction at the site was considered complete in [REDACTED].

The launch site is in a clearing and no security fence can be identified. An erector/shelter is situated in the center of each launch pad and there are two earth-mounded canted buildings inboard of each pad. Three buildings are located in the center of the site: the westernmost is large and earth banked, the middle one is small and earth mounded, and the third is large and earth mounded. There are also two earth-banked missile-ready buildings about 500 feet behind the left launch pad. The inner ready building is canted about 25 degrees and the other is in line with the long

The site support facility consists of an administration/housing section and a housing section. The administration/housing section, on both sides of the access road about 3,000 feet south-southeast of the launch site, consists of 5 large barracks-type buildings, 6 administration-type buildings, 9 smaller buildings, and 2 buildings under construction. The housing section, about 2,000 feet south of the launch site, is probably the old construction camp. It consists of 10 small barracks-type buildings, one L-shaped building, 5 small structures, and one building under construction. There is a small vehicle/equipment pool in the southeast corner of the administration/housing section.

LAUNCH AREA E

Launch Area E (56-48N 40-10E), in a wooded area 13.4 nm southwest of the complex support facility, consists of a completed Type IIF launch

site and a site support facility (Figure 2). The site was first seen on photography of [REDACTED] and can be negated on [REDACTED]

25X1D

25X1D

TCS 7559/64
NPIC/R-700/64




FIGURE 1. LAUNCH AREA D.

NPIC: P-987 (R/64)

25X1D

25X1D

25X1D

photography of [REDACTED]
Construction was considered complete in [REDACTED]

The launch site is in a clearing and is enclosed by a security fence. An erector/shelter is situated in the center of each launch pad and there are two earth-mounded canted buildings inboard of each pad. Three earth-

mounded buildings are positioned in line down the center of the site. In addition, there are two small unidentified mounds immediately to the right of the center buildings which may be buried tanks, and a small building to the rear of each pad. There are three earth-banked missile-ready buildings: one in line behind the left pad, the other two behind the right






FIGURE 2. LAUNCH AREA E.

TCS-7559/64
 NPIC/R-700/64

pad, one in line and the other canted out about 25 degrees. A small earth-mounded building is just forward of the right ready buildings. The

The site support facility consists of an administration/housing section and a housing section. The administration/housing section, about 3,500 feet southeast of the site, contains 3 small and 4 large barracks-type buildings, 5 administration-type buildings, and 12 other

25X2



25X1D

FIGURE 3. LAUNCH AREA F.

NPIC J-2959 (8/64)

TCS-7559/64
NPIC/R-700/64

buildings. There is a small vehicle/equipment pool in the northeast corner of this section. The housing section, about 3,000 feet south-

southeast of the launch site, contains 12 small barracks-type buildings, an L-shaped building, and 7 smaller buildings.

LAUNCH AREA F

Launch Area F (56-54N 40-22E), in a wooded area 7.4 nm northeast of the complex support facility, consists of a completed Type IID launch site and a site support facility (Figure 3). It was first seen on photography of [REDACTED] and can be negated on photography of [REDACTED]. Construction at the site was considered complete in [REDACTED].

The launch site is situated in a clearing and no security fence can be identified. An erector/shelter is positioned at the rear-center of each pad and two earth-mounded canted buildings are inboard of each pad. Three earth-mounded buildings are in line down the center of the site and two small unidentified mounds, just to the right of these buildings, may be buried tanks. There is also a small building to the left rear of the site, just off the access

road. There are three earth-mounded missile-ready buildings. Of the two behind the right pad, the inner one is in line and the other is canted outward about 25 degrees. The single ready building behind the left pad is canted outward about 60 degrees.

25X2
25X2

The site support facility consists of an administration/housing section and a housing section. The administration/housing section contains 22 buildings; a small vehicle/equipment pool is in the northeast corner. The housing section, about 2,500 feet south of the site, consists of 21 small barracks-type buildings, 2 L-shaped buildings, and 2 other buildings.


LAUNCH AREA G

Launch Area G (56-46N 40-02E) consists of clearings for a Type IID launch site and for a site support facility (Figure 4). Located in a wooded area 19.1 nm southwest of the complex support facility, the site was first seen on photography of [REDACTED].

This launch area has been abandoned; there

have been neither significant changes nor signs of construction activity since it was first seen. As [REDACTED] only clearings for pads, buildings, and roads are present; no buildings are visible. The complex main road terminates at Launch Area E and only a trail continues on to Launch Area G. No improvement in this trail has been noticed since Launch Area G was first seen.

25X1D



REFERENCES

PHOTOGRAPHY

25X1D

MAPS OR CHARTS

SAC. US Air Target Chart, Series 200, Sheet 0154-19A, 1st ed, Dec 58, scale 1:200,000 (SECRET)

DOCUMENT

1. NPIC. R-205/64, *ICBM Complex, Tsykora, USSR*, Mar 64 (TOP SECRET CHESS RUFF)

REQUIREMENT

UGMC-64 (partial answer)

NPIC PROJECT

N-711/64

~~TOP SECRET~~
Approved For Release 2000/05/09 : CIA-RDP78B04560A002700010031-5

Approved For Release 2000/05/09 : CIA-RDP78B04560A002700010031-5
~~TOP SECRET~~